

15-135-20771-0000

Form CP-3
Rev. 6-4-68

KANSAS



CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Beardmore Oil, Inc.

Complete Address 700 One Twenty Bldg., Wichita, Kansas

Lease Name Shearer "E" Well No. 1

Location C NW NW Sec. 15 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4483'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil

Address Wichita, Kansas License No.

Operation Completed: Hour 4 P Day 12 Month 7 Year 1973

The above well was plugged as follows:

BTD 4483': 8 5/8 csg set at 319' cwc Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 700' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 310' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Murray
Well Plugging Supervisor

INVOICED

DATE 7/13/73
INV. NO. 7631-U