

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 28 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Lario Oil & Gas Company  
Complete Address 301 South Market Wichita, Kansas 67202  
Lease Name Marshall "A" Well No. 8  
Location C E/2 NE SW Sec. 31 Twp. 11 Rge. (E) (W) 17  
County Ellis Total Depth 3668'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Knight Casing Pulling  
Address Box 405 Chase, Kansas 67524 License No. 436  
Operation Completed: Hour 1:30 P Day 26 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 3668' 8 5/8 csg set at 1150' cwc 300 sk.  
5 1/2 csg set at 3644' cw 110 sx cem.  
Filled 5 1/2 csg W/sd (3668'-3620) dumped 4 sk cmt W/dump bailer. (3620-3590)  
Cutoff and recovered 2546' of 5 1/2 csg.  
Filled 8 5/8 csg W/mud to 435' -set rock & sand bridge (435-420)  
Filled with readymix cement from 420' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/29/74

INV. NO. 9788-W

Signed: Leo E. Massey  
Well Plugging Supervisor