

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CSE 1/4

SEC. 31 TWP. 11 RGE. 17 N

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. C-1 Lease _____ Hadley 510 Orphaena Pl

Operator Walters Drg Co Address Wichita, Kans

Field _____ County Ellis

Total Depth 3062 Feet.

Plugging Contractor R & D Pipe Pulling Co & Globe Cementing

Plugging Contractor's License No. 236

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 171' circulated with cement - 5 1/2" at 3057' with 100 sax
cement behind.

Sand to 3050', set 4 sax cement with dump bailer, pulled 2975'

5 1/2" - pumped hole full mud (25 sax Gel), pumped cementing plug to
180', followed by 60 sax cement - cement 180' to 0'.

Mudding and cementing by Globe Cementing Co.

PLUGGING
FILE SEC. 31 TWP. 11 RGE. 17N
BOOK PAGE 76 LINE 15

NOV 10 1954 11-10-54

District Conservation Agent

Date 11-5-54