

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 29-28 County: Ellis

Location: CW $\frac{1}{2}$ NW NE Sec. 31 Twp. 11 Rge. 17 (E) (W) W

Name of Field: _____ Total Depth: 3702

I have this date completed supervision of plugging of:

Lease Name: Hadley Well No. 5

Operator's Full Name: Republic Natural Gas

Complete Address: Box 126 Ellinwood, Kans

Plugging Contractor: Barnes & Sons & Globe Cementing Co

Address: Russell, Kans License No. 9

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 20 Month 4 Year 59

The above well was plugged as follows:

8 5/8" 1081' circulated with cement - 5 1/2" 3697' with 150 sax cement
behind - perforated 3625'.

Filled with sand to 3610', set 4 sax cement with dump bailer, pulled 2900'
5 1/2" to 550', circulated hole with heavy mud through 5 1/2" (Gel), displaced
25 sax cement through 5 1/2" at 550', heavy mud to 180', displaced 25 sax
cement through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: *Edwin Leety*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 211 R. 74
BOOK PAGE 29 LINE 28

4-24-59