

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 133-25 County: Ellis

Location: SW SW SE Sec. 31 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3620

I have this date completed supervision of plugging of:

Lease Name: Hadley Well No. 1

Operator's Full Name: Republic Natural Gas

Complete Address: Box 126 Ellinwood, Kans

Plugging Contractor: Barnes Sons & Globe Cementing Co

Address: _____ License No. 9

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 10 PM Day 25 Month 11 Year 58

The above well was plugged as follows:

10 3/4" at 1053' circulated with cement - 7" 5018' with 250 sax cement

behind- 5 1/2" liner 2290' to 3620' circulated with 100 sax cement.

Lane wells plugs to 3444', perforated 3422'.

Filled with sand to 3410', set + sax cement with dump bailer, pulled

2160' 7" - pumped hole full heavy mud - (55 sax Gel) pumped cementing

plug to 350', followed by 25 sax cement, 20 sax Gel, and capped

with 15 sax cement.

Mudding and cementing by Globe Cementing Co - pump pressure 900# to 500#

Signed: *E. J. Terry*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

STATE CORPORATION COMMISSION

Remarks:

DEC 2 - 1958

PLUGGING
FILE SEC 31 T. 11 R. 17
BOOK PAGE 133 LINE 25

CONSERVATION DIVISION
Wichita, Kansas