

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kearny County. Sec. 18 Twp. 25S Rge. (E) 35 (W)

Location as "NE/CNW&SW&" or footage from lines C NE/4 SE/4

Lease Owner Braden Drilling, Inc. et al

Lease Name Campbell Well No. 1

Office Address 1206 Union National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed July 7 19 61

Application for plugging filed July 7 19 61

Application for plugging approved July 7 19 61

Plugging commenced July 7 19 61

Plugging completed July 7 19 61

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5130 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	620	10 3/4	620	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 125 sacks cement thru drill pipe at 2600'.
Pumped 40 sacks cement thru drill pipe at 600'.
Set bridge plug at 40' and filled hole to bottom of cellar with 20 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Braden Drilling, Inc.
Address 1206 Union National Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. M. Callaway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1206 Union National Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of July, 19 61

My commission expires March 21, 1962
[Signature] Notary Public.



DRILLER'S LOG

Braden Drilling, Inc. et al
 CAMPBELL #1
 C NE/4 SE/4 Sec. 18-25S-35W
 Kearny County, Kansas

Commenced: June 21, 1961

Completed: July 7, 1961

Set 10 3/4" surface casing at 620'
 and cemented with 425 sacks cement.

Sand	130 feet
Sand and clay	500
Hard Shale	620
Shale	985
Red beds	1420
Sand	1685
Red bed and shale	1990
Shale and shells	2404
Shale and lime	2915
Lime	3065
Lime and shale	3553
Chalky Lime & Shale	3685
Lime with chalk	3817
Lime	4103
Lime with chalk	4188
Lime	4375
Lime and shale	4755
Lime	4825
Lime and shale	4961
Lime	5130 Total depth

RECEIVED
 STATE CORPORATION COMMISSION

JUL 14 1961

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct log of the above captioned well, as shown by the daily drilling reports.


 F. M. Callaway

Subscribed and sworn to before me this 10th day of July, 1961.

My commission expires March 21, 1962.


 Helen Schultz, Notary Public