

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH

			x

Locate well correctly on above
Section Plat

Kearny County. Sec. 18 Twp. 25S Rge. 36 ~~XX~~ (W)
Location as "NE/CNW&SW&" or footage from lines C NE/4 NE/4
Lease Owner Pan American Petroleum Corporation
Lease Name Campbell Well No. 1
Office Address Box 432, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-5- 19 66
Application for plugging filed (Verbal) 11-5- 19 66
Application for plugging approved 11-5- 19 66
Plugging commenced 11-5- 19 66
Plugging completed 11-6- 19 66
Reason for abandonment of well or producing formation No productive zones encountered
If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. J. Eves
Producing formation None Depth to top Bottom Total Depth of Well 5100 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8	345	None
				8-5/8	1800	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud 5100-2950
600 Sacks Cement 2950-2300
Heavy Mud 2300-650
20 Sacks Cement 650-600
Heavy Mud 600-40
15 Sacks Cement 40-0

NOV 16 1966
Conservation Division

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Murfin Drilling Company
Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.
I, D. M. Liles (employee of owner) or ~~conservation agent~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D M Liles
Box 432, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of November 19 66

My commission expires February 11, 1968 Ruf Banks Notary Public.

WELL RECORD

A 10x10 grid with a vertical line at column 5 and a horizontal line at row 5. The number 18 is in the cell at (5, 5). An asterisk is in the cell at (10, 10).

NOTARY PUBLIC

FORMATION RECORD

DESCRIBE EACH FORMATION DRILLED. INDICATE THICKNESS, CONTENT AND WHETHER DRY, OR OIL, GAS, OR WATER BEARING.

FORMATION	TOP	BOTTOM	FORMATION	TOP	BOTTOM
Sand, Clay	0	40	Lime, Shale	4635	4678
Sand	40	220	Lime	4678	4725
Sand, Shale	220	330	Lime, Shale	4725	4810
Shale	330	630	Lime	4810	5100
Shale, Red Bed	630	890			
Red Shale	890	1150	Total Depth		5100
Shale	1150	1350			
Shale, Sand	1350	1540			
Shale	1540	1630			
Red Bed	1630	1780			
Anhydrite	1780	1820			
Shale	1820	2245			
Lime, Shale	2245	3130			
Lime	3130	3174			
Lime, Shale	3174	3560			
Lime	3560	3685			
Lime, Shale	3685	3915			
Lime	3915	4635			

(See Above for Continuation)

There were no productive zones encountered as indicated by analytical logging, drilling samples, coring, drill stem tests, wire line formation tests and electrical logs.

Well completed as a dry hole
Plugged and abandoned November 6, 1966