


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kearny County, Sec. 2 Twp. 26 Rge. 35 (X) (W)

Location as "NE/CNW%SW%" or footage from lines. C SW NE
Lease Owner Helmerich & Payne, Inc.
Lease Name Mobil Well No. 1
Office Address Box 558, Garden City, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-4-67 19__
Application for plugging filed 8-4-67 19__
Application for plugging approved 8-4-67 19__
Plugging commenced 8-4-67 19__
Plugging completed 8-4-67 19__
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production - 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves Sublette, Kansas
Producing formation _____ Depth to top - Bottom - Total Depth of Well 5266 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8" casing	4'	813'	8-5/8"	813	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

5266' to 2775' Heavy Rotary Mud
2775' to 2475' Plug & 100 sacks cement
2475' to 700' Heavy Rotary Mud
700' to 600' Plug & 35 sacks cement
600' to 45' Heavy Rotary Mud
45' to 4' Plug & 15 sacks cement
4' to 0 Cellar

Plugging completed 9:00 PM 8-4-67

SEP 11 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rine Drlg Co.
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Finney, ss.
C. A. Richter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. A. Richter

Box 558, Garden City, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of August, 19 67

My commission expires July 1968

Robert N. Boyd
Notary Public.

15-093-20001-0000

C SW NE
SECTION 2-26S-35W
KEARNY COUNTY, KANSAS

MOBIL WELL NO. 1

CONTRACTOR: RINE DRILLING COMPANY, INC.

STARTED: JULY 23, 1967

COMPLETED: AUGUST 5, 1967

LOG

Sand, Gravel, Red Bed	0' - 470'	Totco - 1/4° @ 333'
Red Bed	470' - 817'	Totco - 1/2° @ 817'
Red Bed & Sand	817' - 1590'	Ran 19 jts. 8 5/8 csg. to 814'. Cem. w/ 350 sx. lite wt. poz w/2% c.c. Followed w/150 sx. common w/3% c.c.
Red Bed, Anhydrite, & shale	1590' - 2200'	Totco - 3/4° @ 2219'
Anhydrite, & Shale	2200' - 2696'	
Lime Streaks	2696' - 2853'	
Lime	2853' - 2890'	
Lime & Shale	2890' - 3090'	
Lime Streaks	3090' - 3250'	Totco - 1/2° @ 3101'
Lime & Shale	3250' - 3530'	Totco - 1/4° @ 3406'
Lime Streaks, Soft Lime Streaks	3530' - 3908'	
Lime	3908' - 4012'	
Lime Streaks	4012' - 4105'	
Lime, Shale & Sand	4105' - 4200'	Totco - 1/2° @ 4200'
Lime Streaks & Chert	4200' - 4324'	
Lime	4324' - 4544'	
Lime Streaks	4544' - 4618'	Totco - 3/4° @ 4616'
Lime	4618' - 4807'	
Lime Streaks	4807' - 4850'	
Lime	4850' - 4875'	
Lime Streaks	4875' - 4938'	
Lime	4938' - 5268'	Totco - 1° @ 5116'; 1° @ 5268'.


STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

I, R. M. Green, do hereby certify that the above is a true and accurate log of the Mobil Well No. 1 located C of SW of NE of Section 2-26S-35W, Kearny County, Kansas.


R. M. Green, Secretary-Treasurer

Subscribed and sworn to before me this 9th day of August, 1967.

MOBIL WELL NO. 1
CORPORATION COMMISSION
OCT - 2 - 1967
REGISTRATION DIVISION
Topeka, Kansas


Sam R. Clift, Notary Public

My Commission Expires: 9/4/68.