

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,579-00-00

LEASE NAME Ummel Trust

WELL NUMBER 2

4950 Ft. from S Section Line

2310 Ft. from E Section Line

SEC 25 TWP 16 RGE 22 XX (E) or (W)

COUNTY Ness

Date Well Completed 6/18/91

Plugging Commenced 6/17/91

Plugging Completed 6/18/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rains & Williamson Oil Co., Inc.

ADDRESS 220 W. Douglas, #435, Wichita, KS 67202

PHONE (316) 265-9686 OPERATORS LICENSE NO. 5146

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/17/91 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4400 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
Surface		280'	0'	8-5/8"	280'	None

07-08-1991
JUL 08 1991

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged with 245 sacks 60/40 Pozmix, 6% gel, 1/4# floceal per sack, as follows: 50 sx @ 1760', 80 sacks @ 1150', 30 sx @ 600', 50 sx @ 300', 10 sx @ 40', 15 sx rathole, 10 sx mousehole. P.D. 1:00 a.m. 6/18/91.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rains & Williamson Oil Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Wilson Rains, President of Rains & Williamson Oil Co., Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wilson Rains

(Address) 220 W. Douglas, Suite 435, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 19 91

Juanita M. Green
Juanita M. Green, Notary Public

JUANITA M. GREEN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 10-4-91

Commission Expires: 10-4-91