

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,393-00-00

LEASE NAME Barber

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

3780 Ft. from S Section Line

4050 Ft. from E Section Line

LEASE OPERATOR DCF Exploration

SEC. 35 TWP. 16S RGE. 22 (N/E/S/W)

ADDRESS 940 Wadsworth Boulevard, Suite #100

COUNTY Ness

Lakewood, CO 80215

PHONE#(303) -232-5011 OPERATORS LICENSE NO. 4964

Date Well Completed 10/23/89

Character of Well D&A

Plugging Commenced 10/23/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/23/89

The plugging proposal was approved on 10/23/89 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	224'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mud laden fluid 4430'-1710' 10 sks cement @ 40'
50 sks cement @ 1710' 15 sks in rathole
65 sks cement @ 870'
40 sks cement @ 240'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, Kansas 67665-0506

STATE 10-30-1989
OCT 30 1989

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DCF Exploration

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kelly P. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 89

Glenda R. Tiffin
Glenda R. Tiffin Notary Public

My Commission Expires: February 6, 1992

15-135-23393-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: DCF Exploration
940 Wadsworth Boulevard, Suite #100
Lakewood, Colorado 80215

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Barber

WELL #1

LOCATION: NE SW NW
Section 35-16S-22W
Ness County, Kansas

LOGGERS TOTAL DEPTH: 4435'

ROTARY TOTAL DEPTH: 4430'

COMMENCED: 10/16/89

CASING: 8-5/8" @ 224' w/140 sks cement

ELEVATION: 2373' K.B.

COMPLETED: 10/23/89

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Post Rock	132'	Anhydrite	1719'
Blue Shale	834'	Red Bed	2300'
Dakota Sand	882'	Shale & Lime Stks.	3500'
Red Bed	1152'	Lime & Shale Stks.	4000'
Cedar Hills	1385'	Lime (R.T.D.)	4430'
Red Bed	1678'		

RECORDED
OCT 30 1989
10-30-1989
Wichita, Kansas


STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kelly P. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kelly P. Branum

Subscribed and sworn to before me on October 27, 1989.

My commission expires: February 6, 1992.


GLENDA R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-92


Glenda R. Tiffin, Notary Public