

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

RECEIVED
OCT 06 2003
KCC WICHITA WELL PLUGGING RECORD

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Rains & Williamson Oil Co., Inc.
Address: 220 W. Douglas, Suite 200, Wichita, KS 67202
Phone: (316) 265-9686 Operator License #: 5146
Type of Well: Oil Well Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9/24/03 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. 4616'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-22,191-00-00
Lease Name: BOWER
Well Number: 3
Spot Location (QQQQ): 30' NE - SE - NW - SW
1680 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 5 Twp. 17 S. R. 26 East West
County: Ness
Date Well Completed: 4/7/82
Plugging Commenced: 9/30/03
Plugging Completed: 9/30/03

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	300'	None
				4 1/2"	4615'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Ran tubing to 1503' spotted 25 sx. common, 3% cc. Pulled tubing, perforated 2 shots @ 1200' Pumped 150 sx. 60/40 poz down 4 1/2" casing SIP 200# & 150 sx. 60/40 poz down annulus SIP 100#. Cut 8 5/8" casing & 4 1/2" casing 4' below plow depth.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: 99996
Address: P. O. Box 31, Russell, KS 67665
Name of Party Responsible for Plugging Fees: Rains & Williamson Oil Co., Inc.
State of Kansas County, Sedgwick, ss.

Juanita M. Green (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

PATRICIA A. THOME
Notary Public - State of Kansas
My Appt. Expires 6/18/05

(Signature) Juanita M. Green
(Address) 220 W. Douglas, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 2nd day of October, 2003

Patricia A. Thome My Commission Expires: 6/18/05
Notary Public Patricia A. Thome

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202