

15-135-20125-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County, Sec. 12 Twp. 17 Rge. 21 ~~XXX~~ X (W)

Location as "NE/CNW/SW" or footage from lines C NW SW

Lease Owner National Cooperative Refinery Association

Lease Name Start Well No. 3

Office Address Box 6, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 3-26 19 68

Application for plugging filed 5-18 19 78

Application for plugging approved 5-19 19 78

Plugging commenced 8-11 19 78


Plugging completed 8-11 19 78

Reason for abandonment of well or producing formation Casing Leak

Not enough oil production to pay for repairs

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Cherokee Depth to top 4049 Bottom 4067 Total Depth of Well 4130 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	417'	-0-
				5 1/2"	4129'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sun Oilwell Cementing, Inc. pumped 50 sacks 50/50 Pozmix + 2% Gel - 2 sacks hulls - 30 sacks Gel - Release Plug and pump 50 sacks 50/50 Pozmix + 2% Gel 400# maximum press. Job Complete @ 11:00 a.m. 8-11-78. Plugging instructions by Leo Massey and witnessed by Leo Massey and Earl Baker.

08-25-1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF Kansas, COUNTY OF Barton, ss.

I, J. Gotsche (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *J. Gotsche*

I. J. Gotsche
Box 6, Great Bend, Ks. 67530
(Address)

Subscribed and sworn to before me this 23rd day of August, 1978

My commission expires January 29, 1981

Patricia Schultz
Patricia Schultz Notary Public.



ROTARY DRILLING LOG

15-135-20125-00-00

Operator: National Cooperative Refinery Association
Ruth Start #3
C NW/4 SW/4 12-17S-21W
Ness County, Kansas

Contractor: Omega Drilling, Inc.

Commenced: March 8, 1968
Completed: March 17, 1968

Casing Record:

8 5/8" surface casing cemented at 417' with 125 sacks cement and 2% calcium chloride.

5 1/2" casing cemented at 4129' with 125 sacks of salt saturated 50-50 Pozmix, with 3/4 of 1% CFR2.

FORMATIONS

420	Shale and shells
490	Shale
1435	Shells, shale and sand
1440	Anhydrite
1536	Anhydrite and shale
2404	Shale and lime
2648	Lime
3665	Lime and shale
4010	Lime
4130	Lime and chert
4130	RTD

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1978
05-19-1978
CONSERVATION DIVISION
Wichita, Kansas

We certify that the above log is true and correct to the best of our knowledge and belief.

OMEGA DRILLING, INC.

By F. S. Woodside, Jr.
F. S. Woodside, Jr.
President

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, County of Sedgwick, this 19th day of March, 1968.

Mary L. Lawrence
Mary L. Lawrence, Notary Public