

To: 1 2-6
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App.
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-135-22,059-00-00
C-SW SE, SEC. 34, T 17 S, R 21 W/8
460 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 9860
Operator: Castle Resources Inc.
Name & Address: 1200 E. 27th
Hays, KS 67601

Lease Name Janke Well # 1
County Ness 138.93
Well Total Depth 4275 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 399

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____
Plugging Contractor Allied Cementing License Number _____
Address _____

Company to plug at: Hour: 9 a.m. Day: 6 Month: 2 Year: 19 97

Plugging proposal received from Dean Ives
(company name) Castle Resources Inc. (phone) 913-483-2662

Work: 4 1/2" at 4272' w/125 sx cement, PBSD 4230', Perfs at 4187-91, 4120-27, 4097-4100'
1st plug pump 200 lbs. hulls and 20 sx cement on bottom,
2nd plug perforate at 700', circulate cement to surface.
Check backside.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11 a.m. Day: 6 Month: 2 Year: 1997

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx cement, pressured to 1200#.
2nd plug perforated at 700', pumped one barrel of water and got circulation. Pumped
190 sx cement, circulated.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

I (and _____) observe this plugging.

Signed Michael J. Mason
(TECHNICIAN)

DATE FEB 12 1997
INV. NO. 47569
2-6

02-11-1997