

To: 1 070103
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,181-00-00

C SE SW, SEC. 34, T 17 S, R 21 W
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9732

Lease Name McCormick Well # 34-14

Operator: Apollo Energies
Name & Address
520 Ridgeway
Pratt, KS 67124

County Ness
Well Total Depth 4325 140.36 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Apollo Energies License Number 9732
Address 520 Ridgeway, Pratt, KS 67124

Company to plug at: Hour: 5:00 pm Day: 7 Month: December Year: 19 85

Plugging proposal received from Jim Bier

(company name) Apollo (phone) 316-672-7324

were: 5 1/2" at 4332' PBSD 4283' Perfs at 4201-4190', 4106-4110', CIBP at 4175

1st plug sand back to 4066' and dump 5 sx cement on top of sand through bailer

2nd plug spot 10 sx cement at 1200' through tubing

3rd plug squeeze well with 1 sack hulls, 10 sx gel, 240 sx cement

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:40 pm Day: 7 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4066' and dumped 5 sx cement on top of sand through bailer, 2nd plug spotted 10 sx cement at 1200' through tubing, 3rd plug squeezed well with 1 sack hulls, 10 sx gel, and 240 sx cement through 8 5/8".

Maximum pressure 650 psi and shut in 350 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 813' 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED did not observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE DEC 20 1985

DEC 20 1985

INV. NO. 11657 JAN 15 1986

12-20-1985