

11-5-87

To: 1 070460  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,253-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 6216

Operator: Edward P. Leiker  
Name & Address: HC-32, Box 132  
Hays, KS 67601

SW SW NW, SEC. 32, T 17 S, R 21 W/4E  
2970 feet from S section line  
4950 feet from E section line

Lease Name Casey Well # 1  
County Ness 140.56  
Well Total Depth 4325 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 410

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Edward P. Leiker License Number 6216

Address HC-32, Box 132, Hays, KS 67601

Company to plug at: Hour: 1:45 p.m. Day: 5 Month: 11 Year: 19 87

Plugging proposal received from Ed Leiker

(company name) Edward P. Leiker (phone) 913-625-5310

were: 5 1/2" at 4322' PBDT 2200', Bridge Plug Perfs approximately 4170', Ft. Scott  
1st plug pump 150 sx cement into 5 1/2" casing,  
2nd plug pump 150 sx cement into 8 5/8" annulus.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 p.m. Day: 5 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug-2200', bridge plug,

2nd plug pumped down 5 1/2" with 150 sx cement,

3rd plug pumped down 8 5/8" with 10 sx cement.

Maximum pressure 900 psi and shut in 600 psi - 5 1/2".

Maximum pressure 500 psi and shut in 500 psi - 8 5/8"

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form.) (OVER)

I (did / ~~did not~~) observe this plugging.

INVOICED

Signed Dan Goodrow (TECHNICIAN)

RECEIVED  
NOV 16 1987  
NOV 6 1987  
CONSERVATION DIVISION  
Wichita, Kansas

DATE NOV 20 1987

INV. NO. 18909 11-5