

1050333

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,654 -00-00

C NW SW , SEC. 32 ; T 17 S, R 21 W/X
N SE Corner of
1980 feet from ~~XXX~~ section line
W SE Corner of
4620 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Casey Well # 1- B

Operator: Pickrell Drilling Company

County Ness

Name & Address 110 North Market, Suite 205

Well Total Depth 4287 139.33 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Company License Number 5123

Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 7:30 am Day: 7 Month: September Year: 19 84

Plugging proposal received from Herb French

(company name) Pickrell (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1470' with 50 sx cement

2nd plug at 750' with 50 sx cement

3rd plug at 390' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Richard M. Lucey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00 pm Day: 7 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement, 2nd plug at 750' with 50

sx cement, 3rd plug at 390' with 40 sx cement, 4th & 5th plugs - solid bridge- hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1984
09-17-1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. # 37805

(If additional description is necessary, use BACK of this form.)

INVOICED (check/discard) observe this plugging.

Signed Richard M. Lucey (TECHNICIAN)

DATE 9-26-84

INV. NO. 3860