

15-135-21704-0009 1050061

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-21,704-00-00

150' NW, SE, SE, NW Sec. 7, T 17 S, R 25 W

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Stutz "D" Well # 1

Operator: Chief Drilling Inc
Name & Address: 905 Century Plaza
Wichita KS
67202

County Ness

Well Total Depth 4500 feet

Conductor Pipe: Size _____ feet 146.25

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. Inc License Number _____

Address Box 31 332 W Wichita Ave Russel KS 67665

Company to plug at: Hour: 10:00am Day: 16 Month: November Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Leon Lindenmuth

(company name) Chief Drilling Co. Inc (phone) _____

were: To pump down 4 1/2" production pipe with
Cement until it would not hold anymore.
Then pump down 8 5/8" surface pipe annulus with
Cement until it would not hold any more
For cement use 50/50 pozmix 4% gel 3% cc

Signed Steve Durrant gave
(TECHNICIAN) proposal

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15am Day: 16 Month: November Year: 1983

ACTUAL PLUGGING REPORT Pumped 85sx of cement in 4 1/2" production
casing, reached a maximum pressure of
700 psi and shut it in @ 700 psi. Pumped 4sx hulls
+ 85sx of cement down 8 5/8" surface pipe annulus,
reached a pressure of 900 psi + shut well in at
900 psi.

Remarks: Well had a packer + tubing sanded in at
2623'. Casing had been squeezed between 1350'
+ 1250'

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1983

Signed Richard W. Lacey
(TECHNICIAN)

FORM CP-213
Rev. 9-82

12-9-83
7094-W
CONSERVATION DIVISION
Wichita, Kansas