

4010833

10-30

398
R

091-20318-0000

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202
 TECHNICIAN'S PLUGGING REPORT
 OPERATOR LICENSE # 6339
 OPERATOR: DON KAUFFMAN
 NAME AND 2402 W. DENNIS AVENUE
 ADDRESS OLATHE, KS 66061

API NUMBER 15- ~~OLD WELL~~
SW, SEC. 33, T 13 S, R 23 E
660 FEET FROM SOUTH SECTION LINE
660 4620 FEET FROM EAST SECTION LINE
 LEASE NAME KAUFFMAN WELL # 1
 COUNTY JOHNSON
 WELL TOTAL DEPTH 550 FEET
 CONDUCTOR PIPE: SIZE _____ FEET _____
 SURFACE CASING: SIZE 8 FEET N/A

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SMD WELL _____ D/A _____
 OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR GLAZE DRILLING LICENSE NUMBER 5885
 ADDRESS ROUTE 2, BOX 309A, SPRING HILL, KS 66083

COMPANY TO PLUG AT: HOUR: _____ DAY: 24 MONTH: 10 YEAR: 91

PLUGGING PROPOSAL RECEIVED FROM A. GLAZE

(COMPANY NAME) GLAZE DRILLING (PHONE) 913-764-2625

WERE: PULL 1" AND PACKER, THEN FILL HOLE TD TO SURFACE AND CIRCULATE TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY JACK ROBISON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: _____ DAY: 30 MONTH: 10 YEAR: 91

ACTUAL PLUGGING REPORT PULLED 546' OF 1" WITH PACKER. THEN SHOT 3 HOLES IN 2" AT 360'. THEN RAN 1"

TO 516' AND FILLED 2" BACK TO SURFACE. THEN PULLED 1" AND HOOKED TO 2" AND CIRCULATED CEMENT TO SURFACE

OUTSIDE 2". TOTAL OF 55 SACKS.

NOV 7 1991

CONSERVATION DIVISION

REMARKS: _____
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Jack Robison
 (TECHNICIAN)
 FORM CP-2/3

INVOICED

DATE NOV 25 1991

INV. NO. 33884

10-30

JAN 28 1992