

63 R

4-12-88
API NUMBER 15-135-23,145-00-00

To: 1 070534
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW, SEC. 29, T 17 S, R 21 W/8
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6759

Lease Name Brenner Well # 2
County Ness 140.56
Well Total Depth 4325 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Operator: William Bucklin III
Name & Address 150 California Street, Suite 300
San Francisco, CA 94111

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor William Bucklin III License Number 6759
Address 150 California Street, Suite 300, San Francisco, CO 94111

Company to plug at: Hour: 3:30 p.m. Day: 12 Month: 4 Year: 19 88

Plugging proposal received from Dean Ives
(company name) William Bucklin III (phone) 415-433-7100

were: 5 1/2" at 4324' PBSD 4312' Perfs at 4288-91
1st plug sand back to 4240' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Dan Goodrow & Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 12 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4225' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 125 sx cement.

04-18-1988
APR 18 1988

Maximum pressure 1000 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by Allied. Recovered 1350' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired, observe this plugging.)

Signed Dan Goodrow
(TECHNICIAN)

DATE 4-20-88
INV. NO. 20377