

To: 1 071081
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-14 API NUMBER 15- 135-20,227-00-00 96
C NE SE, SEC. 28, T 17 S, R 21 W 1/4

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988
Operator: Slawson Exploration Company, Inc.
Name & Address 621 N. Robinson, Suite 490
Oklahoma City, OK 73102

1980 feet from S section line
660 feet from E section line
Lease Name Wagner "F" Well # 1
County Ness 136.92
Well Total Depth 4213 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Plains, Inc. License Number 4072
Address P.O. Box 346, Ness City, KS 67560

Company to plug at: Hour: 3 p.m. Day: 14 Month: 7 Year: 19 92
Plugging proposal received from Max Parsons
(company name) Plains, Inc. (phone) 913-798-3995

were: 4 1/2" at 4191' w/100 sx cement. Open hole 4191-4213', DV @ 1454', cemented to surface w/100
1st plug dump 4 sx cement on top of rock at 4213-4157', _____ sx cement
2nd plug pump 15 sx cement down backside,
3rd plug pump 120 sx cement down 4 1/2".

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5 p.m. Day: 14 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT Rock from 4213-4157'

1st plug dumped 4 sx cement on top of rock with bailer,
2nd plug pumped 15 sx cement down backside,
3rd plug pumped 120 sx cement down 4 1/2" to 1000#.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form)

I (did / did not) observe this plugging.

DATE 7-24-92
WELL NO. 35791

Signed Dan Goodrow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
07-22-1992
JUL 22 1992
RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
JUL 22 1992
CONSERVATION DIVISION
Wichita, Kansas