

8-14

4-041916

D-20,269

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-19443-00-01

NW NE SW _____ / 4 SEC. 05, 11 S, 18 W
2310 _____ feet from S section line
3630 _____ feet from E section line

Operator license# 5537

Saline River
Lease: Grazing Association Well # D-1

Operator: Viola E. Brown
d/b/a Kenny Brown Enterprises
Address: 400 N. Washington
P.O. Drawer 340
Plainville, Kansas 67663

County: Ellis 46.31

Well total depth 1425 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 10 Inch 148 feet
W/150 sxs cmt.

Aband. oil well _____, Gas well _____, Input well _____, SWD X, D & A _____

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 14 Month: August Year 1997

Plugging proposal received from: Steve Ruder

Company: Kenny Brown Enterprises Phone: -

Were: 4 1/2" casing set at 1425' w/500 sxs cement. Perfs at 972' - 1072'.
Ordered 80 sxs mid con two with 1/4# F.C. plus 200# hulls.

8-27-97

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 9:30 A.M. Day: 14, Month: August, Year: 1997

Actual plugging report: Rigged up cementers to 4 1/2" casing. Squeezed casing with 50 sxs cement with 400# hulls. Max. P.S.I. 500#. S.I.P. 500#. Rigged cementers to 10" S.P. Squeezed 30 sxs cement with 200# hulls. Max. P.S.I. 100#. S.I.P. 0#. W.A.M. - additional 10 sxs cement down annulus.

Remarks: _____
Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING X _____ Elevation: _____ G.L. _____

I did [X] / did not [] observe the plugging.

Dennis L Hamel
(agent)

Form CP-2/3

INVOICED

100

DATE 8-29-97

INV. NO. 48881