

4-110087

E-27,056

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-22,310-0002

N2 S2 NW /4 SEC. 05, 11 S, 18 W
3630 feet from S section line
3960 feet from E section line

115.70

Operator license# 5537
Operator: Kenny Brown Enterprises

3/13

Lease: S.V.G.A. Well # 1
(Saline Valley Grazing Association)
County: Ellis

Address: P.O. Box 340
Plainville, Kansas 67663

Well total depth 3560 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 171 feet

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Kenny Brown Enterprises License# 5537

Address: P.O. Box 340 - Plainville, Kansas 67663

Company to plug at: Hour: 1:00 P.M. Day: 13 Month: March Year: 2000

Plugging proposal received from: Steve Ruder

Company: Kenny Brown Enterprises Phone: 785-434-7236

Were: Plug according to KCC Rules & Regulations.
Ordered 350 sxs cement and 800# hulls.

Plugging Proposal Received by: Richard Williams

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:30 P.M., Day: 13, Month: March, Year: 2000

Actual plugging report: 8 5/8" S.P. set at 171' w/130 sxs cement. 4 1/2" casing at 3559' with 175 sxs cement. Squeezed at 826' - 796' w/380 sxs. Tied to 4 1/2" casing and pumped 40 sxs cement with no hulls, followed by 115 sxs cement with 700# hulls to Max. P.S.I. 400#. S.I.P. 0#. Tied to 8 5/8" x 4 1/2" annulus and squeezed 45 sxs cement to Max. P.S.I. 250#. S.I.P. 100#. Total of 200 sxs SMD cement with 700# hulls.

Remarks: Swift Cementing. Stewart Tank - Water.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 2058 GL

I did [X] / did not [] observe the plugging.

INVOICED
DATE: 3/22/00
INV. NO. 061457

Ragan M...
RECEIVED
STATE CORPORATION COMMISSION
Form CP 273

MAR 21 2000

CONSERVATION DIVISION
Wichita, Kansas

(R)

KENNY BROWN ENTERPRISES #1 SALINE VALLEY 5-11-18W
 DRAWER 340 GRAZING C N/2 S/2 NW
 PLAINVILLE, KS 67663

CONTR DREILING OIL, INC. CTY ELLIS
 GEOL LARRY GRAY FIELD RICHARDS

E 2063 KB CM 2/23/81 CARD 6/18/81 IP P 55 80 & 70 BWPD
 2058 GL ISSUED KC 3435-3523 OA
 API 15-051-22,310

+	+
+	+

SMP	TOPS	DEPTH	DATUM
ANH		1386	+ 677
TOP		3042	- 979
HEEB		3263	-1200
TOR		3279	-1216
LKC		3305	-1242
BKC		3538	-1475
RTD		3560	-1497
NO LOG			

8-5/8" 171/130sx, 4 1/2" 3559/175sx
 DST-(1) 3311-3355 (LKC)/TIMES NA,
 REC 210' HG&OCM, SIP 886-862#,
 FP NA
 DST-(2) 3424-3463 (LKC)/TIMES NA,
 REC 560' HG&OCM, 120' GSY OCW,
 60' GSY OCW, SIP 827-803#, FP
 NA
 MICT - CO, PF (KC) 3435-3523 OA,
 SWB GSO, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

