

6 070384

API NUMBER 15-051-22537-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

100's SE-SE-NW, SEC. 5, T. 11 S, R. 18 W

2870 feet from S section line

320 feet from E section line

Saline River Grazing  
Lease Name Association Well 1 7

TECHNICIAN'S PLUGGING REPORT

Operator License # 5537

Operator: Kenny Brown Enterprises

County ELLIS 115.44

Name & Address Drawer 340

Well Total Depth 3552 feet

Pleinville, Kans.

Conductor Pipe: Size 0 feet

67663

Surface Casing: Size 8 5/8 feet 174

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing Co License Number

Address East Hwy 40 Wap, Kans. 67601

Company to plug at: Hour: 1:00 PM Day: 4th Month: Sept Year: 1985

Plugging proposal received from Kenny Brown

(company name) Kenny Brown Enterprises (phone) 913-434-7236

were: 8 5/8" 174' E.S.R. csg. 1/135" ent., 4 1/2" csg. set @ 3552' 1/175" ent.

Plug Back T.D. 3552', Test's 3300' to 3500', 2nd hole squeezed twice @ 924' to 957' 1/300" ent. total, No Pipe Recovery

Order 200 5K60 / 40 Formix Gel - Co-cl., 9 5K Gel, 4 5K Halls and 4 1/2" Plug.

ELV. 2074' Shaky 1400', Pump in Annulus and 4 1/2" csg. with Pump Truck.

Plugging Proposal Received by Marion Schmidt DOIC (TECHNICIAN)

Plugging Operations attended by Agent: All  Part  None

Operations Completed: Hour: 2:20 PM Day: 4th Month: Sept Year: 1985

ACTUAL PLUGGING REPORT Ordered 200 5K60 / 40 Formix Gel - Co-cl., 9 Gel, 4 Halls + 4 1/2" Plug

Pumped in Annulus 70 5K Cmt. 1/1 5K Halls, Max. Pressure 550 Psi. shut in @ 350 Psi.

Pumped in 4 1/2" csg. 50 5K Cmt. 1/2 5K Halls, 9 5K Gel,

Released plug and 80 5K Cmt, Max. Pressure 600 Psi. shut in at 250 Psi.

Cemented By Halliburton Cmt.

Remarks: (if additional description is necessary, use BACK of this form.)

IN (added) (do not) observe this plugging. STATE CORP. COMMISSION

DATE SEP 10 1985

Signed Marion Schmidt DOIC (TECHNICIAN) 20 585 mgp

INV. NO. 10003

SEP 9 1985

CONSERVATION DIVISION