

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-22313-0000

C N/2 NW 3/4 Sec. 5, T 11 S, R 18 W/2R

feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

feet from W/E section line

Operator License # 5537

Salina River  
Lease Name Grazing Assoc. Well # 4

Operator: Kenny Brown Ent.  
Name & Address  
Plainville KS.

County Ellis  
Well Total Depth 3563 feet PB. 3543  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 172' C.W.C.

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Cementing Co. Account Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 10 AM Day: 19 Month: 9 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Kenny Brown  
(company name) Plainville KS. (phone) \_\_\_\_\_

were: Sept. 19th ordered 300 sx. com. 50/50 permix 6% Gel 3% C.C., 5 sx. hulls, 1-4 1/2" plug, 8 sx. Gel.

Sept. 20th ordered 150 sx. com. 50/50 permix 6% Gel. 3% C.C. Used 35 sx.

Elev. 2050 Anhydrite 1384 Signed Dale J. Baltheizer  
Dakota 1575 K.C. 3284-3524 (TECHNICIAN)

op.

Plugging Operations attended by Agent? All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

ACTUAL PLUGGING REPORT Sept 19th pumped down 4 1/2 csg. 25 sx. com., 25 sx. com. mixed with 2 sx. hulls, 8 sx. Gel. mixed with 3 sx. hulls. Released plug pumped 100 sx. com. on top. Shut 4 1/2 in. Pumped down 8 5/8 150 sx com. Shut 8 5/8 in. Sept 20th showed 4 1/2 plug slipped 400'; pumped down 4 1/2 30 sx. com. Pumped down 8 5/8 5 sx. com.

Remarks: Partial witness - Gib Laiker & Gib Schuck

I hereby certify that the above plugging instructions were given as herein stated and that I (did) (did not) observe this plugging. SFP 24 1984

Signed Dale J. Baltheizer (TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas  
FORM CP-2/1  
Rev. 9-82