

6 010224

API NUMBER 15-051-22,313-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C N¹/₂ NW SW, SEC. 5, T. 11 S, R. 18 W/E
_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5537

_____ feet from W/E section line
Saline River Gazing Assoc.
Lease Name _____ Well # 4

Operator: Kenny Brown Ent.
Name &
Address _____

County Ellis 115.80

Plainville, Ks.

Well Total Depth 3563' P.B. 3543' feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 172 CUC

Abandoned Oil Well XXX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing Company License Number _____

Address Hays, Ks.

Company to plug at: Hour: _____ AM Day: 19 Month: September Year: 19 84

Plugging proposal received from Kenny Brown

(company name) Kenny Brown Ent. (phone) _____

were: Sept. 19th Ordered 300 sks cmt 50/50 pozmix 6% gel 3% cal. cl., 5 sk hulls, 1-4¹/₂"
plug, 8 sks gel

Sept. 20th Ordered 150 sks cmt 50/50 pozmix 6% gel 3% cal. cl., Used 35 sks Elev. 2050

Anhy. 1384 Top Dakota 1575 K.D. 3284-3524

Plugging Proposal Received by Dale F. Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part _____ None _____

Operations Completed: Hour: 9:30 AM Day: 20 Month: September Year: 19 84

ACTUAL PLUGGING REPORT Sept 19th pumped down 4¹/₂" csg. 25 sks cmt, 25 sks cmt mixed with
2 sks hulls, 8 sks gel mixed with 3 sks hulls, released plug pumped 100 sks cmt on top.

Shut 4¹/₂ in, pumped down 8⁵/₈ 150 sks cmt shut 8⁵/₈ in, Sept. 20th showed 4¹/₂ plug slipped 400'

Pumped down 4¹/₂ 30 sks cmg. Pumped down 8⁵/₈ 5 sks cmt

Partial witness - Gib Lieker and Gib Scheck

SEP 24 1984

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVITED observe this plugging.

Signed Dale F. Balthazor
(TECHNICIAN)

9-21-84
28

DATE 9-27-84

INV. NO. 3913

9-20