

7-7-88

1 070558

API NUMBER 15-135-23,259-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION W/2 W/2 NE, SEC. 6, T 17 S, R 25 W/2  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3960 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5815

Lease Name Hopkins Well # 1

Operator: C & R Drilling Company  
Name:  
Address: 410 17th Street, Suite 1140  
Denver, CO 80202

County Ness 146.67  
Well Total Depth 4513 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor R & C Drilling Company License Number 9087

Address P.O. Box 296, Hays, KS 67601

Company to plug at: Hour: 9:45 p.m. Day: 6 Month: 7 Year: 1988

Plugging proposal received from Rick Finnesy

(company name) R & C Drilling Company (phone) 913-625-4548

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1903-38'

1st plug at 1940' with 50 sx cement, 2nd plug at 1150' with 80 sx cement,

3rd plug at 330' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:15 a.m. Day: 7 Month: RECEIVED Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 1940' with 50 sx cement.

2nd plug at 1150' with 80 sx cement, JUL 12 1988

3rd plug at 330' with 40 sx cement,

4th plug at 40' with 10 sx cement, CONSERVATION DIVISION Wichita, Kansas

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

I, ~~OPERATOR~~ did not observe this plugging.

Signed Dan Goodrow (TECHNICIAN)

INVOICED  
DATE 7-21-88  
INV. NO. 21508

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date June 27 1988 month day year

API Number 15-135-23259-00 000

OPERATOR: License # 5815 Name C. & R. Drilling Co. Address 410 17th St., Suite 1140 City/State/Zip Denver, CO 80202 Contact Person Les Olson Phone 303/623-6144

NE4 Sec. 6 Twp. 17 S, Rg. 25 West 3960 Ft. from South Line of Section 2310 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County Ness Well # 1

CONTRACTOR: License # 9087 Name R. & C. Drilling City/State Hays, Kansas

Lease Name Hopkins Ground surface elevation 2551 feet MSL

Well Drilled For: Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 100 Depth to bottom of usable water 750/1000

Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate 1-2 X Surface pipe planned to be set 300

Conductor pipe required

Projected Total Depth 4550 feet

Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 6-21-88 Signature of Operator or Agent Title Prod. Manager

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2

This Authorization Expires 12-23-88 Approved By 6-23-88

EFFECTIVE DATE: 6-28-88

Move in 6-28-88 set 8 5/8" to 300'

NE4 Sec. 6 Twp. 17 S, Rg. 25 West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ possible perm. forma. feet depth with 25 sxs of 60/40 Pozmix 6¢ gel, 3¢ cc accros Anhydrite feet depth with 20 sxs of Dakota form. 50' below feet depth with 10 sxs of Surf. pipe 50' in 50' out feet depth with 40 sxs of wiper plug at 40' feet depth with 10 sxs of Rathole with sxs (b) Mousehole with 10 sxs

PUSHER John Rich Zimney TD 4513 FORMATION Miss SURFACE PIPE 8 5/8" @ 315' ANHYDRITE 1903' ELEVATION 2551' STARTING TIME & DATE 9:45 PM COMPLETION TIME & DATE 1:15 AM 1st PLUG @ 1940 FT. W/ 50 SX 2nd PLUG @ 1150 FT. W/ 80 SX 3rd PLUG @ 330 FT. W/ 40 SX 4th PLUG @ 46 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ CEMENT COMPANY TECHNICALIAN

RECEIVED STATE CORPORATION COMMISSION JUL 12 1988 CONSERVATION DIVISION Wichita, Kansas

60/40 6% 25