

1 060773

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-20,809-00-00

C SW NE, SEC. 6, 'T 17 S, R 25 W/R  
3300 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Hopkins Well # 1

Operator: Thunderbird Drilling Co.

County Ness 146.32

Name & Address P. O. Box 18407

Well Total Depth 4502 feet

Wichita, KS 67218

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 202

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 17 Month: January Year: 19 86

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4484' Open Hole

1st plug sand back to 4430' and dump 5 sx cement on top of sand through bailer

2nd plug pump 50 sx cement, 10 sx gel, and 100 sx cement down 5 1/2" casing.

3rd plug pump 50 sx cement down Annulus

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:00 pm Day: 17 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4430' and dumped 5 sx cement on top of sand through bailer, 2nd plug pumped 50 sx cement, 10 sx gel, 100 sx cement down 5 1/2" casing. 3rd plug pumped 50 sx cement down Annulus.

5 1/2" Maximum pressure 500 psi and shut in 200 psi

RECEIVED  
STATE CORPORATION COMMISSION

8 5/8" Maximum pressure 400 psi and shut in 100 psi

JAN 27 1986

No recovery. Could not get casing loose. Whot at 1200' and shot at 1000'

CONSERVATION DIVISION

Remarks: Used 60/ 40 Pozmix 6% gel 3% cc by Allied.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
(and ~~operator~~) observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

GATE JAN 30 1986

INV. NO. 12194