

1 060937

FEB 23 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-21,141-00-00
C SW NE, SEC. 4, T 17 S, R 25 W/EK
3300 feet from S section line
1980 feet from E section line
Lease Name Mollenkamp Well # 1
County Ness 145.96
Well Total Depth 4491 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 322

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Operator: DaMar Resources, Inc.
Name & Address P.O. Box 70
Hays, KS 67601

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor DaMar Resources License Number 9067

Address P.O. Box 70, Hays, KS 67601

Company to plug at: Hour: 1 p.m. Day: 23 Month: 2 Year: 1987

Plugging proposal received from John Schrippers

(company name) DaMar Resources, Inc. (phone) 913-625-0020

were: 5 1/2" at 4486' PBD 4491' Open hole

1st plug pump 3 sx hulls, 30 sx cement, 27 sx gel, 125 sx cement down 5 1/2",

2nd plug pump 150 sx cement down 8 5/8" annulus.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 23 Month: 2 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls, 30 sx cement, 27 sx gel, and 125 sx cement down 5 1/2",

2nd plug pumped 18 sx cement down annulus, pressured up and blew ring.

Maximum pressure 1500 psi and shut in 600 psi - 5 1/2".

No recovery.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED 16211 Observe this plugging.

DATE 2-26-87

INV. NO. 16211

Signed Paul A. Tuttle
(TECHNICIAN)