

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22852-00-01
Spot: E2SWNW Sec/Twnshp/Rge: 4-17S-25W
3415 feet from S Section Line, 3090 feet from E Section Line
Lease/Unit Name: FULLER Well Number: 1
County: NESS Total Vertical Depth: 4502 feet

Operator License No.: 31174
Op Name: BIG HORN OIL CO., INC.
Address: PO BOX 263
GREAT BEND, KS 67530

Conductor Pipe: Size feet: 8 1/2" 32
Surface Casing: Size 8.625 feet: 366 WITH 255 SX CMT
Production: Size 4.5 feet: 4532 WITH 565 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/12/2002 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: ROGER Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP 400# HULLS - 50 SX CMT - 10 SX GEL - 100 SX CMT. PRESSURE TEST. PUMP 35 SX CMT DOWN BACKSIDE AND PRESSURE TEST.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/14/2002 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4460'. PERFS AT 4476-85 & 4375-78'. PORT COLLAR AT 1880' WITH 450 SX CMT. PUMPED DOWN 4 1/2" WITH 400# HULLS - 50 SX CMT - 10 SX GEL - 100 SX CMT. DID NOT PRESSURE UP. WELL ON VACUUM. TIED ONTO 8 5/8" X 4 1/2" AND PUMPED 35 SX CMT. PRESSURED TO 500# AND HELD. TIED ONTO 4 1/2" CASING AND PUMPED 15 SX CMT. DID NOT PRESSURE UP. WILL COME BACK AND TOP OFF. 08/14/02: WELL WAS 1000' DOWN. TOPPED OFF WELL WITH 50 SX CMT.

RECEIVED
AUG 19 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

INVOICE # AUG 15 2002

DATE 8-19-02

INV. NO. 2003060243 MP

Form CR-243