

1 070281

JAN 05 1987

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION N/2 S/2 NE/4, SEC. 4, T 17 S, R 25 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,088-00-00  
3630 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067 & 6390

Lease Name Mollenkamp Well # 1

Operator: DaMar Resources, Inc. & McDonald-  
Name & Wallace Petroleum Company, Inc.  
Address \_\_\_\_\_

County Ness 147.19

Well Total Depth 4529 feet

P.O. Box 70

Conductor Pipe: Size \_\_\_\_\_ feet

Hays, KS 67601

Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Western Kansas Drilling License Number 4083

Address Box 126, Hays, KS 67601

Company to plug at: Hour: 9 p.m. Day: 4 Month: 1 Year: 1987

Plugging proposal received from Frank Taggart

(company name) Western Kansas Drilling (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1885-1916'  
Elevation 2536'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at Base Dakota with 100 sx cement,

3rd plug at 370' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:15 a.m. Day: 5 Month: 1 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 1916' with 50 sx cement,

2nd plug at 890' with 100 sx cement,

3rd plug at 370' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION  
JAN 14 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

**INVOICED** (if not observe this plugging.

Signed Dan Goodrow  
(TECHNICIAN)

DATE 1-12-87

INV. NO. 15871

FEB 10 1987

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12 20 86 month day year

API Number 15-135-23,088

OPERATOR: License # 9067 and 6390
Name DaMar Resources, Inc. and McDonald-Wallace
Address P. O. Box 70
City/State/Zip Hays, KS 67601
Contact Person Daniel F. Schippers
Phone (913) 625-0020

N/2 S/2 NE/4 Sec. 4 Twp. 17 S. Rg. 25 East
3630 Ft. from South Line of Section
1320 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License #
Name Unknown Western Drilling
City/State
Well Drilled For: Oil SWD Infield Mud Rotary Pool Ext. Air Rotary Wildcat Cable
Well Class: Infield Pool Ext. Wildcat
Type Equipment: Mud Rotary Air Rotary Cable

Nearest lease or unit boundary line 990 feet
County Ness
Lease Name Mollenkamp Well # 1
Ground surface elevation 2520 est. feet MSI
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 2 X
Depth to bottom of fresh water 120
Depth to bottom of usable water 800 975
Surface pipe planned to be set 320
Projected Total Depth 4,500 feet
Formation Mississippian

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications.
cementing will be done immediately upon setting production casing
Date 12/11/86 Signature of Operator or Agent Title President
For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt.
This Authorization Expires 6-12-87 Approved By 12-12-86

342.5t 878

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, feet depth with, and sx of. Includes handwritten notes like 'But by 5:30' and 'Banded at 100'.

Handwritten log entries:
PUSHER Frank Taggart
TD 4529' FORMATION MISS.
SURFACE PIPE 8 5/8" @ 347'
ANHYDRITE 1885-1916 ELEVATION 2536'
STARTING TIME & DATE 9:00 PM 1-4-87
COMPLETION TIME & DATE 12:15 AM 1-5-87
1st PLUG @ 1916 FT. W/ 50 SX
2nd PLUG @ 890 FT. W/ 100 SX
3rd PLUG @ 370 FT. W/ 50 SX
4th PLUG @ 40 FT. W/ 10 SX
RAI HOLE CIRCULATED W/ 15 SX
6 1/4" poz. 6% gel
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied
TECHNICIAN Dan Goodrey Sawhney

STATE CORPORATION COMMISSION
JAN 12 1987
CONSERVATION DIVISION
Wichita, Kansas