

1090159

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20.958-0000

C W/2 SW SE SEC. 12, T 16 S, R27 W/R

660 feet from N/S section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Evel Well # 2

Operator: A. L. Abercrombie, Inc.

County _____ Lane _____

Name & Address 801 Union Center

Well Total Depth 4480 145.60 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 24 Month: April Year: 1984

Plugging proposal received from Tony Martin

(company name) Abercrombie (phone) 316-262-1841

were: _____ to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2040' with 50 sx cement 3rd plug at 990' with 50 sx cement

2nd plug at 1500' with 50 sx cement 4th plug at 450' with 40 sx cement

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:30 pm Day: 24 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2040' with 50 sx cement, 2nd plug at 1500'

with 50 sx cement, 3rd plug at 990' with 50 sx cement, 4th plug at 450' with 40 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx

cement, 7th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 07 1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form)

(If not) observe this plugging.

Signed R. Barluttan
(TECHNICIAN)

DATE 5-7-84

INV. NO. 1408

MAY 09 1984