

1060176

TO: STATE CORPORATION COMMISSION

10-14

API NUMBER 15-101-20,897 -00-00  
C SE SW SEC. 12, T 16 S, R 27 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME EVEL WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY LANE

OPERATOR LICENSE # 9615

WELL TOTAL DEPTH 4531 FEET

OPERATOR: JOE GERSTNER OIL COMPANY PRODUCTION CSG: SIZE 5 1/2" @ 4530' WITH SX

NAME AND ADDRESS 302 E SYCAMORE SURFACE CASING: SIZE 8 5/8" @ 300' WITH SX

ADDRESS NESS CITY, KS 67560

INVOICED

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ DATE 10/26/99

OTHER WELL AS HEREINAFTER INDICATED INV. NO. 60739

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 12:30 PM DAY: 14 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MONTE

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4185-87, 4213-16, 4508-11, 4515-20

SANDED TO 4080' WITH 5 SX CEMENT. RUN PACKER TO 1200' PRESSURED TO 500# AND HELD. PERFORATED AT 1250'. RAN TUBING TO 2000' & PUMPED 60 SX CEMENT WITH 300# HULLS. PULLED TO 1250' AND MIXED 60 SX CEMENT THEN 40 SX CEMENT WITH 200# HULLS. NO CIRCULATION. PULLED TUBING WENT DOWN BACKSIDE WITH 100 SX CEMENT. PRESSURED TO 300#. SHUT IN WITH 100#. PUMPED DOWN CASING WITH 100 SX, SHUT IN WITH 100#. PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 6:00 PM DAY: 14 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT SANDED TO 4080' WITH 5 SX CEMENT. RAN PACKER TO 1200' PRESSURED TO 500# AND HELD. PERFORATED AT 1250'. RAN TUBING TO 2000' & PUMPED 60 SX CEMENT WITH 300# HULLS. PULLED TO 1250' AND MIXED 60 SX CEMENT THEN 40 SX CEMENT WITH 200# HULLS. NO CIRCULATION. PULLED TUBING WENT DOWN BACKSIDE WITH 100 SX CEMENT. PRESSURED TO 300# SHUT IN WITH 100#. PUMPED DOWN CASING WITH 100 SX CEMENT. SHUT IN WITH 100#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID)OBSERVE THIS PLUGGING.

SIGNED Michael Maier CONSERVATION DIVISION WICHITA, KANSAS FORM CP-273 RECEIVED OCT 29 1999