

1 030418

4-26

API NUMBER 15- 101-20,694 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NW SE, SEC. 3, 7 16 S, R 27  
2310 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30742  
Operator: Palomino Petroleum, Inc.  
Name & Address: 4924 SE 84th St.  
Newton, KS 67114

Lease Name Mendenhall Well # 2  
County Lane  
Well Total Depth 4540 147.55  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 327

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A   
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 26 Month: 4 Year: 19 94

Plugging proposal received from Manny Boatright  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

logs: 5 1/2" at 4534' w/250 sx cement, Perfs 3696-4458' (11 sets)  
1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 80 sx cement at 1250', 3rd plug pump 40 sx cement at 800',  
4th plug pump 50 sx cement at 360', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:45 a.m. Day: 26 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 3650' and dumped 5 sx cement on top of sand through bailer,

2nd plug spotted 50 sx cement at 1250',  
3rd plug spotted 80 sx cement at 800',  
4th plug spotted 50 sx cement at 360',  
5th plug at 40' with 10 sx cement. Cement circulated.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1636' of 5 1/2" casing.  
If additional description is necessary, use BACK of this form.  
(old / XXXXXX) observe this plugging.

INVOICED  
DATE MAY 22 1994  
40399

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 02 1994  
CONSERVATION DIVISION  
Wichita, Kansas  
Signed [Signature] (TECHNICIAN)