

1 090241

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,006 -00-00

SE NE SW, SEC. 10, T 16 S, R 27 W/EX
1430 feet from N SE Corner of
W W/2S section line
2720 feet from W SE Corner of
W/2E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5420

Lease Name Broughton Well # 1
County Lane

Operator: White & Ellis Drilling, Inc.
Name & Address 401 E. Douglas, Suite 500
Wichita, KS 67202

Well Total Depth 4450 144.63 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 752

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420
Address 401 E. Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 20 Month: October Year: 19 84

Plugging proposal received from Steve Zink
(company name) White & Ellis (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe

- 1st plug at 1980' with 50 sx cement
- 2nd plug at 1410' with 50 sx cement
- 3rd plug at 810' with 40 sx cement
solid bridge
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by R. B. Barluttan (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 11:00 am Day: 20 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1980' with 50 sx cement, 2nd plug at 1410' with 50
sx cement, 3rd plug at 810' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx
cement.

RECEIVED
OCT 30 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc
(if additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

Signed R. B. Barluttan SD (TECHNICIAN)

10-29-84
4527