

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00576-00-02
Spot: NENESW Sec/Twnshp/Rge: 28-14S-19W
2330 feet from S Section Line, 2976 feet from E Section Line
Lease Name: WEBER Well #: ~~SWS~~ 1-SWDW
County: ELLIS Total Vertical Depth: feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF		204		

Well Type: SWD UIC Docket No: D21280.0 Date/Time to Plug: 05/03/2012 8:00 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: JOE BARENS Company: OUTLAW WELL SERVICE LLC Phone: (785) 650-2399

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/200 # hulls.
DV tool @ 1410' w/300 sx
PBTB 1062'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/03/2012 12:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:


Outlaw well service ran in hole with tubing 923.51. Schippers rigged to 5 1/2" casing. Mixed and pumped 135 sx cement w/ 200 # hulls mixed in to circulate cement to surface.
Pulled tubing. Topped off 5 1/2" casing with 10 sx cement. Hole standing full.
Rigged to 8 5/8" casing and pumped 5 sx cement to pressure w/ 175 psi and 175 shut in pressure.

Remarks: SOS TICKET # 571 Control # 2010042001

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

MAY 07 2012

MAY 07 2012

RECEIVED

MAY 14 2012

KCC WICHITA

Form CP-2/3