

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21455-00-00
Spot: E2NESE Sec/Twnshp/Rge: 21-23S-16W
1883 feet from S Section Line, 415 feet from E Section Line
Lease Name: JAMES TRUST A Well #: 1
County: PAWNEE Total Vertical Depth: 4125 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2490		
CIBP		3590		WITH 2 SX CMT
SURF	8.625	265		WITH 210 SX CMT
PROD	5.5	4120	0	WITH 215 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/01/2012 10:00 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: JUSTIN TROUT Company: HARTMAN OIL Phone: (785) 796-3995

Proposed Plugging Method: CIBP @ 2490' & 2 SX CMT. PEROFRATE 5 1/2" @ 1060'. CIRCULATE CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/01/2012 10:40 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CIBP ALREADY SET AT 2490'. BAILED 2 SX CMT ON TOP OF PLUG. PERFORATED 5 1/2" @ 1025'. PUMPED 290 SX CMT CIRCULATING CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4054	4058		
3671	3676		
3644	3648		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

MAY - 3 2012

KCC DODGE CITY

RECEIVED
MAY 09 2012
KCC WICHITA

5/22/12
Form CP-2/3

MAY