

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21263-00-00
Spot: N2SENESE Sec/Twnshp/Rge: 31-15S-10W
1780 feet from S Section Line, 330 feet from E Section Line
Lease Name: ZVOLANEK Well #: 31-1
County: ELLSWORTH Total Vertical Depth: 3300 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: 140 W WICHITA AVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	234		150 SX
PROD	5.5	3299	1071	225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/02/2011 8:00 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: FRANK SCHULTE Company: _____ Phone: (785) 483-1534

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 09/07/2011 5:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 2900' & CAPPED WITH 2 SX OF CEMENT. PERF HOLES SHOT @ 1324', SPOTTED 35 SX OF CEMENT. SHOT CASING OFF @ 1071' SPOTTED 35 SX OF CEMENT, PULLED CASING TO 300' CIRCULATED TO SURFACE WITH 60 SX OF CEMENT, 9/7/11 CEMENT FELL BACK TO 70', TOPPED WITH 15 SXS.

Perfs:

Top	Bot	Thru	Comments
3091	3095		
3020	3022		
2946	2950		

Remarks: CEMENTING DONE BY QUALITY WELL CEMENTING, TICKET #3852

Plugged through: CSG

District: 02

Signed B. J. Hope
(TECHNICIAN)

RECEIVED
MAY 09 2012
KCC WICHITA