

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22683-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 24-8S-18W  
4950 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: HINDMAN-FEE HOBART Well #: 3  
County: ROOKS Total Vertical Depth: 3437 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 260        |             | 160 SX   |
| SURF   | 8.625 | 261        |             |          |
| PROD   | 4.5   | 3449       |             | 175 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/08/2012 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Revd. from: BRYAN HESS Company: HESS OIL CO Phone: (620) 241-4640

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
DV tool @ 1200' w/350 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/08/2012 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2611', pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 1822', pumped 95 sx cement w/200 # hulls to circulate to surface.  
Pulled all tubing, topped off 4 1/2" casing w/35 sx cement.  
Hooked to 8 5/8" x 4 1/2" annulus. Pressured to 1000psi.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3400 | 3406 |      |          |
| 3386 | 3388 |      |          |
| 3350 | 3355 |      |          |
| 3331 | 3332 |      |          |
| 3289 | 3412 |      |          |

Remarks: ALLIED TICKET # 56109

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Pat Bedore  
(TECHNICIAN)

CM

MAY 09 2012

RECEIVED Form CP-2/3

MAY 14 2012

KCC WICHITA