

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20605-00-00
Spot: NWSWSENV Sec/Twnshp/Rge: 26-3S-21W
2201 feet from N Section Line, 1504 feet from W Section Line
Lease Name: ARLENE MULDER Well #: 1-26
County: NORTON Total Vertical Depth: 3923 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213		160 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/01/2012 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 230 sx 60/40 pozmix - 4% gel with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE
Date/Time Plugging Completed: 05/01/2012 1:45 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st plug @3813 w/25 sx
2nd plug @1967 w/25 sx
3rd plug @1267 w/100 sx
4th plug @263 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: QUALITY OIL

Plugged through: DP

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

✓ 5/22/12

RECEIVED

MAY 14 2012

Form CP-2/3

MAY 02 2012

KCC WICHITA