

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-02000-00-01  
Spot: SWSESE Sec/Twnshp/Rge: 4-35S-3W  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: SCHMIDTZ Well #: 3-3  
County: SUMNER Total Vertical Depth: 4822 feet

Operator License No.: 34357  
Op Name: ATLAS OPERATING LLC  
Address: 15603 KUYKENDAHL, STE 200  
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	4326		
PROD	7	4816		500 SX
SURF	10.75	605		450 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/26/2012 12:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (832) 509-8713

Proposed Plugging Method: SAND BACK PERFS & CAP WITH 7 SKS CMT. REC-CASING. CIRC CMT 650'-0'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/26/2012 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SANDED WELL BACK TO 3547' & CAPPED WITH 7 SKS CMT. NO RECOVERY. FLOWED 35 BBLS OIL UP BACKSIDE. PUMPED 215 SKS CMT IN 10 3/4" - 7" ANNULAS. SHUT IN WITH 350#. LET SET OVER NITE. RAN 2" TUBING TO 650' INSIDE 7" CASING. PUMPED 115 SKS CMT. RAN 1" IN ANNULAS & PUMPED 15 SKS CMT.

Perfs:

Top	Bot	Thru	Comments
4324	4328	CSG	

Remarks: QUALITY WELL SERVICE - TA NOV

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

5/22/12

RECEIVED

MAY 21 2012

KCC WICHITA

JK