

8-21-88

To: 1 051080
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,480-00-00

NE NE NE, SEC. 19, T 19 S, R 28 W/E

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020

Lease Name Hineman "C" Well # 1-19

Operator: Rine Exploration Company

County Lane 151.94

Name & Address 300 West Douglas, Suite 645

Well Total Depth 4675 feet

Wichita, KS 67202-2904

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 21 Month: 8 Year: 19 88

Plugging proposal received from Tony Martin

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2160'

1st plug at 2160' with 50 sx cement, 2nd plug at 1280' with 80 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5 a.m. Day: 21 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement,

2nd plug at 1280' with 80 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1988

08-23 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

(CHECK / did not) observe this plugging.

DATE 8-24-88

Signed Richard W. Lutz
(TECHNICIAN)

INV. NO. 21912

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: 08/01/88

API Number 15-101-21,480-00-00

OPERATOR: License # 5020
Name: Rine Exploration Company
Address: Suite #645, 300 W. Douglas
City/State/Zip: Wichita, KS 67202-2904
Contact Person: M. Bradford Rine
Phone: 316/262-5418

NE 1/4 NE 1/4 NE 1/4 Sec. 19 Twp. 19 S. Rg. 28
4950 Ft. from South Line of Section
330 Ft. from East Line of Section

CONTRACTOR: License # 5422
Name: Abercrombie Drilling, Inc.
City/State: Wichita, KS 67202

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet

Well Drilled For: Well Class: Type Equipment:
[X] Oil [] Storage [] Infield [X] Mud Rotary
[X] Gas [] Inj [X] Pool Ext. [] Air Rotary
[] OWWO [] Expl [] Wildcat [] Cable

Lease Name: Hineman 'C' Well # 1-19
Ground surface elevation 2785 (L&S) feet MSL

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Domestic well within 330 feet: yes [] no [X]
Municipal well within one mile: yes [] no [X]

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 07/28/88 Signature of Operator or Agent W. D. Hess Title Vice-President

Depth to bottom of fresh water 200-100
Depth to bottom of usable water 2200-1300

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X (2)
This Authorization Expires 1-28-89 Approved By LKM 7-28-88

Surface pipe by Alternate: 1-X
Surface pipe planned to be set 230
Conductor pipe required -0-

Projected Total Depth 4700 feet
Formation Mississippian

EFFECTIVE DATE: 8-2-88

SPUD 8/13/88
Set 230' 8/2 -

NE 1/4 NE 1/4 NE 1/4 Sec. 19 Twp. 19 S. Rg. 28 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep 2100' or formation with 50 sacks feet of 60-40 poz, 2% gel, 3% cc
2nd plug @ ft. deep 1300' or formation with 80 sacks feet of 60-40 poz, 2% gel, 3% cc
3rd plug @ ft. deep 330' or formation with 40 sacks feet of 60-40 poz, 2% gel, 3% cc
4th plug @ ft. deep 40' or formation with 10 sacks feet of 60-40 poz, 2% gel, 3% cc
5th plug @ ft. deep or formation with feet of

(2) Rathole to surface minus 5 feet - 15 sacks (b) Mousehole to surface minus 5 feet - 10 sack

PUSHER Tony Nistina
TD 4675 FORMATION M.S.S
SURFACE PIPE 8 5/8 @ 267
ANHYDRITE 2160 ELEVATION 2785
STARTING TIME & DATE 2:00am 8-21-88
COMPLETION TIME & DATE 5:00am 8-21-88
1st PLUG @ 2160 FT. W/ 50 SX
2nd PLUG @ 1280 FT. W/ 80 SX
3rd PLUG @ 300 FT. W/ 50 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied
TECHNICIAN Paul Luthi

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1988
08-23-1988
CONSERVATION DIVISION
Wichita, Kansas