

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04839-00-01
Spot: NENENESE Sec/Twnshp/Rge: 36-19S-14W
2384 feet from S Section Line, 287 feet from E Section Line
Lease Name: VAUGHAN RUSSELL Well #: 1
County: BARTON Total Vertical Depth: 3520 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 9427 E. CROSS CREEK
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3236		
PLG3	5.5	3544		w/150 sxs cmt
PROD	5.5	3544		150 SX
SURF	8.5	400		100 SX

Well Type: SWD UIC Docket No: E27291.1 Date/Time to Plug: 05/14/2012 11:00 AM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: ROCH MILLER Company: EDISON OPERATING Phone: (620) 786-5161

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2012 4:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1600', 760' and 375'.
Ran tubing to 3236'. Pumped 50 sx cement into stinger packer.
Pulled tubing to 3225'. Pumped 14 sx gel.
Pulled tubing to 1650'. Pumped 90 sx cement w/200 # hulls.
Pulled tubing to 750'. Circulated cement to surface on casing and surface pipe w/175 sx cement and 200 # hulls.
Pulled tubing. Topped off w/15 sx cement.

Perfs:

Top	Bot	Thru	Comments
3253	3257		

RECEIVED
MAY 18 2012
5-18-12
KCC WICHIT.

Remarks: COPE ACID AND CEMENTING

Plugged through: CSG TDC

District: 04

Signed Bruce Rodie
(TECHNICIAN)
cc to UIC 5/18

CM