

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22643-00-00  
Spot: SWNENENW Sec/Twnshp/Rge: 14-34S-38W  
507 feet from N Section Line, 2176 feet from W Section Line  
Lease Name: MID-AMERICA CATTLE Well #: 14 #3  
County: STEVENS Total Vertical Depth: 6750 feet

Operator License No.: 5278  
Op Name: EOG RESOURCES, INC.  
Address: 3817 NW EXPRESSWAY STE 500  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6100		WITH 2 SX CMT
CIBP		6190		
CIBP		6250		
CIBP		6540		
SURF	8.625	1713		WITH 555 SX CMT
PROD	5.5	6722	1770	WITH 185 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2012 12:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 6100' WITH 5 SX CMT. PLUG AT 1750' WITH 20 SX GEL & 50 SX CMT. PLUG AT 610' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/01/2012 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 6100' WITH 2 SX CMT. SHOT AT 2410', UNABLE TO POH. RE-CUT AT 1770' & POH WITH CASING. 1ST PLUG AT 1750' WITH 20 SX GEL & 120 SX CMT. 2ND PLUG AT 610' WITH 60 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6584	6590		
6256	6260		
6206	6234		
6147	6158		

RECEIVED  
MAY 18 2012  
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED  
MAY - 8 2012

KCC DODGE CITY

Signed

Jack MacLaskey  
(TECHNICIAN)

5/24/12  
Form CP-2/3  
RWY