

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22544-00-01
Spot: E2E2SE Sec/Twnshp/Rge: 1-31S-38W
1342 feet from S Section Line, 264 feet from E Section Line
Lease Name: NETTIE MAY Well #: 1 #1
County: STEVENS Total Vertical Depth: 6000 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4656		WITH 5 SX CMT
CIBP		5300		
SURF	8.625	1694		WITH 480 SX CMT
DVT		3143		
PROD	4.5	5501	2109	WITH 280 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/04/2012 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4656' WITH 5 SX CMT. SPOT 30 SX CMT OVER DV TOOL @ 3193'. PLUG AT 1724' WITH 120 SX CMT. PLUG AT 730' WITH 60 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 05/04/2012 2:00 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

SET CIBP @ 4656' WITH 5 SX CMT. SPOTTED 30 SX CMT OVER DV TOOL AT 3193'. SHOT CASING OFF AT 2109'. PLUG AT 1750' WITH 120 SX CMT. PLUG AT 730' WITH 60 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5338	5342		
5324	5328		
4706	4712		

RECEIVED
MAY 18 2012
5-18-12
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED

MAY - 8 2012

KCC DODGE CITY

Signed

Jack Macclaskey
(TECHNICIAN)

5/24/12
Form CIV 2/3

1317