

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21825-00-00  
Spot: W2SESESE Sec/Twnshp/Rge: 13-28S-34W  
337 feet from S Section Line, 344 feet from E Section Line  
Lease Name: ROLLIE Well #: 13 #1  
County: HASKELL Total Vertical Depth: 5650 feet

Operator License No.: 5278  
Op Name: EOG RESOURCES, INC.  
Address: 3817 NW EXPRESSWAY STE 500  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4150		WITH 10 SX CMT
PROD	5.5	4399	1999	WITH 110 SX CMT
SURF	8.625	1658		WITH 480 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/09/2012 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4171' WITH 5 SX CMT. PULL CASING. PLUG AT 1688' WITH 100 SX CMT. PLUG AT 850' WITH 60 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/09/2012 1:30 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

SET CIBP @ 4150' WITH 10 SX CMT. CIRCULATED HOLE WITH MUD. 1ST PLUG AT 1688' WITH 100 SX CMT. 2ND PLUG AT 850' WITH 60 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4221	4245		

RECEIVED  
MAY 18 2012  
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jack MacClaskey  
(TECHNICIAN)

RECEIVED  
MAY 16 2012  
KCC DODGE CITY

5/24/12  
Form CP-2/3

RONNIE