

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20824-00-00  
Spot: NESWNWNW Sec/Twnshp/Rge: 7-20S-34W  
4377 feet from S Section Line, 4791 feet from E Section Line  
Lease Name: MINNIX Well #: 1-7  
County: SCOTT Total Vertical Depth: 5082 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4565		WITH 2 SX CMT
SURF	8.625	223		WITH 175 SX CMT
DVT		2377		WITH 310 SX CMT
PROD	4.5	4750	0	WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2012 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JAMES ESQUIVEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: SET CIBP @ 4565' WITH 2 SX CMT. PLUG AT 2400' WITH 15 SX CMT. PLUG AT 1290' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/13/2012 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4565' WITH 2 SX CMT. 1ST PLUG AT 2406' WITH 15 SX CMT. FULL CIRCULATION. CIRCULATE CASING FULL OF CMT FROM 1296' USING 75 SX CMT. TOO H WITH TBG & TOP OFF CASING WITH 15 SX CMT. PUMP 2 SX CMT DOWN ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
4616	4626		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

RECEIVED

MAY 03 2012

KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED

APR 24 2012

KCC DODGE CITY

Form CP-2/3

5/07/12

BOW