

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-26182-00-00  
Spot: NESWSWSE Sec/Twnshp/Rge: 15-11S-18W  
350 feet from S Section Line, 2230 feet from E Section Line  
Lease Name: PEAVEY A Well #: 3  
County: ELLIS Total Vertical Depth: 1586 feet

Operator License No.: 33263  
Op Name: BOWMAN, WILLIAM F. DBA THE BILL  
Address: 2640 W RD  
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		170 sx

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2012 12:00 AM  
Plug Co. License No.: 34535 Plug Co. Name: INTEGRITY DRILLING CO., LLC  
Proposal Rcvd. from: BILL BOWMAN Company: BOWMAN OIL Phone: \_\_\_\_\_

Proposed Plugging Method: Circulation lost in salt section while drilling well.

Plugging Proposal Received By: CASE MORRIS  
Date/Time Plugging Completed: 03/29/2012 11:00 AM

WitnessType: NONE  
KCC Agent: CASE MORRIS

Actual Plugging Report:

Lost circulation in salt section @1586'. Went on vacuum.  
Added following 80 bbl premixes:  
23 sx gel, 30 hulls, 18.75# LCM/bbl  
18 sx gel, 35 hulls, 21.87# LCM/bbl  
18 sx gel, 30 hulls, 15 multi seal, 26.25# LCM/bbl  
18 sx gel, 30 hulls, 25 multi seal, 31.25# LCM/bbl  
15 sx gel, 35 hulls, 9 multi seal, 26.37# LCM/bbl

No circulation.  
Dumped 33 burlap sacks, 9 bags of hulls, 1 bag multi seal. Pushed material down with bit and put 18 sx gel, 30 hulls on top. No circulation.  
Lost approximately 550-600 bbl of fluid.  
Spotted 50 sx "hot" cement (common) @1250'. Plug lost.  
Spotted 100 "hot" cement (common) @1350'. Plug lost.  
Dumped 100 gallons chat gravel. Filled up 5'.  
Dumped 120 gallons chat gravel. Filled up 15'.  
Ran in to 1250'. Got returns. Spotted 25 sx gel and 50 sx cement.  
Let set for 9 hours. Ran in and tagged hard @1310'.  
Pulled up to 1250' and spotted 30 sx cement.  
Pulled to 650' and spotted 100 sx cement.  
Pulled to 275' and spotted 40 sx cement.  
Pulled to 40' and spotted 10 sx cement.  
Rathole 30 sx.

Perfs:

Remarks: ALLIED CEMENTING

Plugged through: DP

RECEIVED  
MAY 04 2012  
KCC WICHITA

District: 04

Signed

Case Morris  
(TECHNICIAN)

5/07/12

MAY 02 2012