

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22365-00-00
Spot: SWNENW Sec/Twnshp/Rge: 6-15S-13W
4328 feet from S Section Line, 3623 feet from E Section Line
Lease Name: WITT Well #: 7
County: RUSSELL Total Vertical Depth: 3052 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 N MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	712		325 SX
PROD	5.5	3052		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2012 9:30 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: MICHAEL MCGLOCKLIN Company: SHIELD OIL PRODUCERS, INC Phone: (785) 483-3141

Proposed Plugging Method: Ordered 350 sx of 60/40 pozmix 4% gel w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/01/2012 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated @ 1450', 700' and 325'.
Ran tubing to 2661'. Pumped 100 sx of cement w/200 # hulls.
Pulled tubing to 1550'. Pumped 100 sx of cement w/200 # hulls.
Pulled tubing to 300'. Pumped 40 sx of cement
Cement circulated out the back side and fluids out the braden head.
Closed back side. Pumped 50 sx of cement. Casing head was leaking. Shut down and POOH.
Hooked to the casing and pumped 40 sx of cement.
Cement circulated out the braden head. Total of 90 sx of cement between the 5 1/2" and 8 5/8" casing.

Perfs:

Remarks: QUALITY CEMENTING TICKET # 406

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

RECEIVED

MAY 04 2012

KCC WICHITA

Form CP-2/3

MAY 22 2012