

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20992-00-01  
Spot: NESWSW Sec/Twnshp/Rge: 23-11S-15W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: DREHER Well #: 1  
County: RUSSELL Total Vertical Depth: 3333 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LAR  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	229		150 SX
PROD	4.5	3330		100 SX
PROD	4.5	3333		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2012 8:30 AM  
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.  
Proposal Rcvd. from: BRIAN CABLE Company: LARSON OPERATING CO. Phone: (620) 653-7368

Proposed Plugging Method: Ordered 350 sx of 60/40 pozmix 4% gel w/500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/01/2012 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated @ 1600'.  
Ran tubing to 3262'. Pumped 60 sx of cement w/100 # hulls.  
Pulled tubing to 2456'. Pumped 80 sx of cement w/150 # hulls.  
Pulled tubing to 1256'. Pumped 75 sx of cement w/150 # hulls.  
Cement circulated.  
POOH. Hooked to braden head and pumped 250 psi.  
Hooked up to casing and pumped 10 sx of cement @ 300 psi.

Perfs:

Top	Bot	Thru	Comments
3330	3333		

Remarks: QUALITY CEMENTING TICKET # 499

Plugged through: TBG

District: 04

Signed

RAY DINKEL

(TECHNICIAN)

CM

MAY 02 2012

RECEIVED

Form CP-2/3

MAY 04 2012

KCC WICHITA