

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22635-00-00  
Spot: NESWNWNE Sec/Twnshp/Rge: 12-21S-6W  
4728 feet from S Section Line, 2263 feet from E Section Line  
Lease Name: KREHBIEL TRUST Well #: 1-12  
County: RICE Total Vertical Depth: 3515 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 200 W DOUGLAS AVE STE 520  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	350		300 sx cement
COND	13.375	80		65 sx cement
PROD	5.5	3444		75 sx cement

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/30/2012 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKES TESTING & SALVAGE Phone: (620) 562-0895

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: PATRICK SHIELDS  
Date/Time Plugging Completed: 04/30/2012 2:00 PM

Witness Type: PARTIAL  
KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU ON 4-27-12, CK BOTTOM. SAND PERFS OFF TO ABOVE 3300' AND CAP WITH 5 SX'S CEMENT. TAG SAND @ 3300' ON 4-30-12. CUT CASING OFF AT 2600' AND PULL TO 750' AND PUMP 35 SX'S CEMENT. PULL CASING TO 450' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3348	3354	CSG	

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-39550.

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
MAY 09 2012  
KCC WICHITA

5/14/12  
Form CP-2/3

1/3K